ADDENDUM NO. 1

Water Tower Altitude Valves
St. John the Baptist Parish, Louisiana

DATE ISSUED: July 16, 2013
BID DATE: July 23, 2013

EES PROJECT NO. 1304

This Addendum shall be considered as included and/or amended in the original Contract Documents and shall take precedence over any part of the original documents or previous addendum in conflict therewith. This Addendum contains 1 page. All bidders shall ensure all sheets of this Addendum are enclosed. If sheets are missing from this Addendum, it is the responsibility of the Bidder to notify the Engineer seventy-two (72) hours prior to the bid date and time.

STATE OF LOUISIANA
OSCAR J. BOUDREAUX, JR.
REG. No. 18859
REGISTERED PROFESSIONAL ENGINEER IN CIVIL & ENVIRONMENTAL ENGINEERING

7/16/13

I. DRAWINGS

Sheet 2

Add the following note to Sheet 2 of the drawings:

"27. All pipe penetrations to the elevated water storage tank shall comply with all provisions of AWWA Standards D100, Welded Carbon Steel Tank for Water Storage. In particular, all welding and pipe penetrations on the rise column shall apply."