
ADDENDUM NO. 2

MAIN WASTEWATER PUMP STATION REHABILITATION

PEC PROJECT NO. 11161

Prepared for:


ST. JOHN THE BAPTIST PARISH
1811 W. AIRLINE HIGHWAY
LAPLACE, LA 70068

Prepared by:



PEC
PROFESSIONAL
ENGINEERING
CONSULTANTS
CORPORATION

7600 Innovation Park Drive
Baton Rouge, LA 70820
P: 225.769.2810
F: 225.769.2882
PECLA.com



ADDENDUM NO. TWO (2)

DATE ISSUED: Friday, February 15, 2019

BID DATE: Thursday, February 21, 2019

BID TIME: 2:45 PM (Local Time)

This addendum shall be part of the Contract Documents as provided in the Instructions to Bidders.

The following items are issued to add to modify and clarify the Contract Documents. These items shall have full force and effect as the Contract Documents, and the costs involved shall be included in the Bid Prices.

Acknowledge receipt of the Addendum by inserting its number on Page 00300-1 of the Bid Documents. Failure to do so may subject the Bidder to disqualification.

IN THE SPECIFICATIONS

Make the following "pen and ink" corrections:

Addendum No. 1 Cover Sheet, correct spelling of "Wastewater" in project title.

QUESTIONS/CLARIFICATIONS

Clarifications:

- The upstream manhole will not be lined or coated.
- All ductile iron piping shall be ceramic epoxy lined.

Questions:

Please provide the specification for the I/O cards needed to be installed in the existing Telemetry Panel.

The PLC is an Allen Bradley Micro 1400; the I/O cards need to match.

Please provide the specification for the proposed instrumentation.

The level transmitter needs to be ultrasonic and classified for the service.

What is the platform the owner is currently running at the plant?

National Instruments Lookout HMI