SEWER MAINLINE REHABILITATION TABLE

STREET	BEGINNING MANHOLE	ENDING MANHOLE	PIPE DATA						POINT REPAIR					CIPP				MAINLINE SERVICE LINE CONNECTION AT POINT REPAIR	CIPP RESTORED SERVICE LINE CONNECTIONS	MANHOLE CONNECTION
			LENGTH (L.F.)	SIZE (IN)	DEPTH (L.F.)	DEPTH CODE	SURFACE COVER	TYPE	DISTANCE FROM BEGINNING MANHOLE	BEGIN	END	PR- (L.F.)	DESCRIPTION	BEGIN	END	OBSTRUCTIONS	TOP HATS			
Toni St.	R-30-75	R-30-74	401.5	8	7.3	B	Asphalt	VCP						0.0	401.5	2	1		7	
Toni St.	R-30-74	R-30-73	396.2	8	9.3	C	Asphalt	VCP	278.2	275.0	281.0	6.0	Offset Joint							
W. 10th St./Hwy 637	R-30-42	R-30-41	333.4	8	7.8	B	Asphalt	VCP						0.0	333.4	1	2		2	
W. 10th St./Hwy 637	R-30-41	R-30-40	279.7	8	7.9	B	Asphalt	VCP						0.0	279.7				2	
W. 3rd St.	R-30-95	R-30-94	304.9	8	6.6	B	Asphalt	VCP						0.0	304.9		4		4	
W. 3rd St.	R-30-94	R-30-93	318.1	8	7.4	B	Asphalt	VCP CIP	33.1	30.0	36.0	6.0	Defective service line tap					1		
W. 3rd St.	R-30-94	R-30-93	318.1	8	7.4	B	Asphalt	VCP CIP	147.5	144.0	150.0	6.0	Defective service line tap					1		
W. 3rd St.	R-30-93	R-30-92	315.9	8	8.2	C	Asphalt	VCP						0.0	315.9		3		4	
W. 3rd St.	R-30-92	R-30-91	305.1	8	9.2	C	Asphalt	VCP	108.0	105.0	111.0	6.0	Defective service line tap					1		
W. 3rd St.	R-30-92	R-30-91	305.1	8	9.2	C	Asphalt	VCP						0.0	305.1		1		4	
W. 3rd St.	R-43-27	R-30-95	322.3	8	5.9	A	Asphalt	VCP						0.0	322.3		1		6	
W. 4th St.	R-30-71	R-30-70	315.0	8	7.1	B	Asphalt	VCP	268.6	265.0	271.0	6.0	Infil Weeper							
W. 4th St.	R-30-70	R-30-69	311.1	8	7.9	B	Asphalt	VCP						0.0	311.1	2	2		6	
W. 4th St.	R-30-69	R-30-68	323.0	8	8.3	C	Asphalt	VCP						0.0	323.0	4			6	
W. 4th St.	R-43-21	R-43-20	332.3	8	4.2	A	Asphalt	VCP						0.0	332.3		2		6	
W. 4th St.	R-30-72	R-43-18	298.0	8	5.4	A	Asphalt	VCP						0.0	12.0					
W. 4th St.	R-43-19	R-43-18	141.2	8	4.4	A	Asphalt	VCP						0.0	141.2	2	1		1	
W. 5th St.	R-43-13	R-30-67	336.4	8	7.3	B	Asphalt	VCP	158.6	155.0	161.0	6.0	Broken service line tap					1		
W. 5th St.	R-43-13	R-30-67	336.4	8	7.3	B	Asphalt	VCP						0.0	336.4	1	1		6	
W. 5th St.	R-43-14	R-43-13	345.8	8	6.1	B	Asphalt	VCP	300.9	298.0	304.0	6.0	Defective service line tap					1		
W. 5th St.	R-43-14	R-43-13	345.8	8	6.1	B	Asphalt	VCP	313.0	310.0	316.0	6.0	Defective service line tap							1
W. 5th St.	R-43-15	R-43-14	296.8	8	5.1	A	Asphalt	VCP	5.6	0.0	8.0	8.0	Offset Pipe							1
W. 5th St.	R-43-14	R-43-15	296.8	8	5.1	A	Asphalt	VCP						0.0	296.8		2		6	
W. 6th St.	R-43-12	R-43-11	272.1	8	4.4	A	Asphalt	VCP						0.0	6.0					
W. 6th St.	R-43-12	R-43-11	272.1	8	4.4	A	Asphalt	VCP	30.5	27.5	37.5	10.0	Defective service line taps					2		
W. 6th St.	R-43-11	R-43-12	272.1	8	4.4	A	Asphalt	VCP	34.9	31.0	37.0	6.0	Crushed service line tap					1		
W. 6th St.	R-43-11	R-43-12	272.1	8	4.4	A	Asphalt	VCP	113.1	109.0	115.0	6.0	Defective service line tap					1		
W. 6th St.	R-43-10	R-30-66	385.3	8	7.0	B	Asphalt	VCP	288.1	283.0	289.0	6.0	Infil Weeper							
W. 6th St.	R-43-10	R-30-66	385.3	8	7.0	B	Asphalt	VCP	329.5	326.5	332.5	6.0	Defective service line tap					1		
W. 6th St.	R-43-11	R-43-10	374.9	8	5.4	A	Asphalt	VCP	27.8	25.0	31.0	6.0	Defective service line tap							
W. 6th St.	R-43-11	R-43-10	374.9	8	5.4	A	Asphalt	VCP						0.0	374.9	1	3		9	
W. 7th St.	R-30-60	R-30-59	327.1	8	9.2	C	Asphalt	VCP	208.6	205.0	211.0	6.0	Defective service line tap					1		
W. 7th St.	R-30-57	R-30-58	98.5	8	9.2	C	Asphalt	VCP	83.6	80.5	98.5	18.0	Broken/Sag							
W. 7th St.	R-30-57	R-30-58	98.5	8	9.2	C	Asphalt	VCP						0.0	98.5				1	
W. 7th St.	R-30-55	R-30-62	266.5	8	11.3	D	Asphalt	VCP						0.0	266.5				2	
W. 7th St.	R-30-61	R-30-62	157.3	10	11.3	D	Asphalt	AC						0.0	157.3					1
W. 7th St.	R-43-8	R-30-60	326.0	8	6.3	B	Asphalt	VCP						0.0	326.0				4	
W. 7th St.	R-43-9	R-43-8	266.7	8	6.3	B	Asphalt	VCP CIP	106.5	103.5	109.5	6.0	Defective service line tap					1		
W. 7th St.	R-43-9	R-43-8	266.7	8	6.3	B	Asphalt	VCP CIP	136.8	134.0	140.0	6.0	Defective service line tap					1		
W. 7th St.	R-43-9	R-43-8	266.7	8	6.3	B	Asphalt	VCP CIP	204.6	202.0	208.0	6.0	Defective service line tap					1		
W. 8th St.	R-43-7	R-43-6	224.2	8	5.5	A	Asphalt	VCP						0.0	224.2		2		5	
W. 8th St.	R-30-51	R-30-50	139.9	8	11.8	D	Asphalt	Lined Conc.						0.0	139.9	4				
W. 8th St.	R-30-54	R-30-53	427.1	8	7.9	B	Asphalt	VCP	117.3	114.0	120.0	6.0	Defective service line tap					1		
W. 8th St.	R-30-54	R-30-53	427.1	8	7.9	B	Asphalt	VCP	180.1	177.0	183.0	6.0	Defective service line tap					1		
W. 8th St.	R-30-54	R-30-53	427.1	8	7.9	B	Asphalt	VCP	276.5	274.0	280.0	6.0	Defective service line tap					1		
W. 8th St.	R-30-54	R-30-53	427.1	8	7.9	B	Asphalt	VCP	309.9	306.0	312.0	6.0	Defective service line tap					1		
W. 8th St.	R-30-53	R-30-52	354.5	8	9.0	C	Asphalt	VCP						0.0	354.5				6	
W. 8th St.	R-43-7	R-43-6	224.2	8	5.5	A	Asphalt	VCP	94.9	91.0	97.0	6.0	Defective service line tap					1		
W. 8th St.	R-43-6	R-43-5	326.5	8	5.9	A	Asphalt	VCP CIP	180.2	177.0	185.0	8.0	Defective service line taps					2		
W. 8th St.	R-43-6	R-43-5	326.5	8	5.9	A	Asphalt	VCP CIP	269.1	266.0	274.0	8.0	Defective service line taps					2		
W. 9th St.	R-30-46	R-30-45	295.1	8	5.7	A	Asphalt	VCP	38.7	35.0	41.0	6.0	Defective service line tap					1		
W. 9th St.	R-30-45	R-30-44	276.9	8	8.2	C	Asphalt	VCP						0.0	276.9		1		4	

UTILITY WARNING

The Contractor is advised that existing overhead and underground utilities such as (but not limited to) electrical lines and poles, telephone cable, gas lines, water lines, and sanitary sewers exist in the rights-of-way where the proposed improvements are to be installed, all in accordance with the provisions of R.S. 38:2223. It shall be the Contractor's responsibility to protect these existing utilities during the construction of the work to be installed under this Contract and any damage to the existing utilities caused by the negligent acts of the Contractor shall be repaired by the Contractor at his expense. The Contractor shall contact Louisiana One (1) Call (1-800-272-3020) a minimum of 48 hours prior to beginning construction in the work area.

STATE OF LOUISIANA
GERALD W. BABIN, JR.
REG. No. 28785
PROFESSIONAL ENGINEER
IN
CIVIL ENGINEERING
11/08/13

DATE	REVISIONS	BY	DATE	REVISIONS	BY
01/13	ISSUED FOR BID	CWB			

ST. JOHN THE BAPTIST PARISH
OWNER

WASTEWATER LINE REHABILITATION
WASTEWATER LINE REHABILITATION TABLES
TITLE

DESIGNED: GWB/KEF
DRAWN: DJM
CHECKED: CMH
APPROVED: GWB
SCALE: N.T.S.
DATE: JANUARY 2013

PROFESSIONAL ENGINEERING CONSULTANTS CORPORATION
7600 GSRI Avenue • Baton Rouge, LA 70820 • Phone: 225.769.2810 • Fax: 225.769.2882

PROJECT NO. 10929-2
SHEET NO. 11

G:\10929\10929-2\Used for Bid\10929_09 - 11 Rehab Table.dwg [SHT 11] Jan 28, 2013 - 3:05pm by Joe