SEWER MAINLINE REHABILITATION TABLE

STREET	BEGINNING MANHOLE	ENDING MANHOLE	PIPE DATA						POINT REPAIR					CIPP				MAINLINE SERVICE LINE CONNECTION AT POINT REPAIR	CIPP RESTORED SERVICE LINE CONNECTIONS	MANHOLE CONNECTION
			LENGTH (L.F.)	SIZE (IN)	DEPTH (L.F.)	DEPTH CODE	SURFACE COVER	TYPE	DISTANCE FROM BEGINNING MANHOLE	BEGIN	END	PR-(L.F.)	DESCRIPTION	BEGIN	END	OBSTRUCTIONS	TOP HATS			
Bethlehem	R-44-83	R-44-89	183.3	8	6.4	B	Asphalt	VCP	163.0	158.0	166.0	8.0	Broken Pipe/Roots					1		
Chad B. Baker	R-32-15	R-32-16	421.7	8	5.0	A	Asphalt	VCP						0.0	421.7		2		8	
Chad B. Baker	R-32-16	R-32-17	443.7	8	6.9	B	Asphalt	VCP						0.0	443.7	3	2		6	
Chad B. Baker	R-32-17	R-32-18	409.5	8	7.2	B	Asphalt	VCP						0.0	409.5		1		6	
Chad B. Baker	R-32-18	R-45-42	447.1	8	10.6	D	Asphalt	VCP						0.0	447.1		2		3	
Chad B. Baker	R-45-43	R-45-42	392.2	8	10.6	D	Asphalt	VCP						0.0	393.2	4	2		4	
Chad B. Baker	R-45-44	R-45-43	375.9	8	9.4	C	Asphalt	VCP						0.0	375.9		2		2	
Chad B. Baker	R-45-45	R-45-44	292.6	8	8.8	C	Asphalt	VCP	91.8	88.0	94.0	6.0	Defective service line tap					1		
Chad B. Baker	R-45-45	R-45-44	292.6	8	8.8	C	Asphalt	VCP						0.0	292.6				7	
Chad B. Baker	R-45-46	R-45-45	295.0	8	6.5	B	Asphalt	VCP/PVC	23.0	20.0	26.0	6.0	Pipe offset (Old Point Repair)					1		
Chad B. Baker	R-45-46	R-45-45	295.0	8	6.5	B	Asphalt	VCP/PVC	172.4	170.5	176.5	6.0	Defective service line tap					1		
Cop Dr.	R-30-68	R-30-73	265.5	8	9.3	C	Asphalt	VCP	14.3	0.0	23.0	23.0	Sag							
E. 19th St.	R-44-85	R-44-84	297.8	8	5.1	A	Asphalt	VCP	2.6				Cracked Pipe	0.0	6.0					
E. 19th St.	R-44-86	R-44-85	248.4	8	5.0	A	Asphalt	VCP	100.4	97.0	103.0	6.0	Defective service line tap					1		
E. 19th St.	R-44-86	R-44-85	248.4	8	5.0	A	Asphalt	VCP	243.5	240.4	248.4	8.0	Broken Pipe							1
E. 20th St.	R-44-91	R-44-90	276.8	8	5.7	A	Asphalt	VCP	156.4	153.4	159.4	6.0	Cracked Pipe							
E. 20th St.	R-44-94	R-31-93	310.5	8	9.7	C	Asphalt	VCP	305.0				Cracked Pipe	300.0	310.0					
E. 21st St.	R-44-98	R-44-99	356.6	8	6.0	A	Asphalt	VCP	258.0	249.0	265.0	12.0	Sag / Cracked Pipe							
E. 21st St.	R-44-101	R-44-100	305.4	8	4.8	A	Asphalt	VCP						0.0	305.4		1		7	
E. 21st St.	R-44-96	R-44-95	54.8	8	7.9	B	Asphalt	VCP						0.0	54.8					
E. 21st St.	R-44-97	R-44-96	326.1	8	5.9	A	Asphalt	VCP						0.0	326.1	4	1			
E. 22nd St.	R-31-93	R-31-76	298.0	8	10.6	D	Asphalt	VCP	86.4	83.0	105.0	22.0	Collapsed Pipe	0.0	8.0			1		
E. 22nd St.	R-31-76	R-31-77	136.3	8	11.3	D	Asphalt	VCP						0.0	136.3					
E. 22nd St.	R-44-102	R-44-103	398.3	8	4.4	A	Asphalt	VCP	175.0	163.0	187.0	24.0	Offset Pipe/Broken Pipe					1		
E. 22nd St.	R-44-102	R-44-103	398.3	8	4.4	A	Asphalt	VCP						0.0	398.3	1	2		5	
E. 22nd St.	R-44-103	R-44-104	413.9	8	5.5	A	Asphalt	VCP	134.3	131.0	137.0	6.0	Defective service line tap					1		
E. 22nd St.	R-44-104	R-44-103	413.9	8	5.5	A	Asphalt	VCP	47.0	42.0	54.0	12.0	Sag							
E. 22nd St.	R-44-104	R-44-103	413.9	8	5.5	A	Asphalt	VCP						0.0	413.9		2		7	
E. 23rd St.	R-44-110	R-44-112	381.7	8	8.4	C	Grass	VCP	186.0	176.0	198.0	22.0	Sag					2		
E. 23rd St.	R-44-110	R-44-112	381.7	8	8.4	C	Grass	VCP						0.0	381.0	2	1		6	
E. 23rd St.	R-44-114	R-44-113	278.2	8	7.2	B	Asphalt	VCP	108.9	106.0	112.0	6.0	Defective service line tap					1		
E. 23rd St.	R-44-109	R-31-79	199.4	10	14.5	F	Grass/Dirt	VCP CIP	60.0	48.0	72.0	24.0	Sag							
E. 23rd St.	R-45-6	R-44-114	451.3	8	6.4	B	Asphalt	VCP	6.8	0.0	8.0	8.0	Infil Weeper							1
E. 23rd St.	R-45-6	R-44-114	451.3	8	6.4	B	Asphalt	VCP	299.2	296.0	302.0	6.0	Infil Weeper					1		
E. 24th St.	R-31-81	R-31-82	401.8	8	7.2	B	Asphalt	PVC	318.7	315.0	321.0	6.0	Infil Weeper							
E. 24th St.	R-31-83	R-31-84	363.3	8	9.6	C	Asphalt	PVC	355.9	352.0	363.0	11.0	Infil Weeper at Service Tap					1		1
E. 24th St.	R-31-84	R-45-1	303.5	8	11.3	D	Asphalt	PVC	83.6	80.0	86.0	6.0	Defective service line tap					1		
E. 24th St.	R-31-84	R-45-1	303.5	8	11.3	D	Asphalt	PVC	124.9	122.0	128.0	6.0	Deformed pipe							
E. 24th St.	R-45-4	R-45-3	213.1	8	7.4	B	Asphalt	PVC	190.0	186.0	194.0	8.0	Joint offsets							
E. 24th St.	R-45-10	R-45-5	399.8	8	5.2	A	Asphalt	PVC	64.0	61.0	67.0	6.0	Cracked pipe							
E. 24th St.	R-45-10	R-45-5	399.8	8	5.2	A	Asphalt	PVC	177.5	174.5	180.5	6.0	Infil Runner					1		
E. 24th St.	R-45-3	R-45-2	375.0	8	7.4	B	Asphalt	VCP CIP	340.7	338.0	344.0	6.0	Infil Weeper							
E. 25th St.	R-45-26	R-45-25	271.9	8	4.8	A	Asphalt	VCP	2.0	0.0	8.0	8.0	Broken Pipe/Infil Runner							1
E. 25th St.	R-45-26	R-45-27	374.8	8	3.5	A	Asphalt	VCP	3.0	0.0	10.0	10.0	Broken Pipe/Roots							1
E. 25th St.	R-45-26	R-45-27	374.8	8	3.5	A	Asphalt	VCP						0.0	374.8	2			6	
E. 26th St.	R-32-8	R-32-9	335.3	8	5.1	A	Asphalt	VCP						0.0	335.3		2		7	
E. 26th St.	R-32-9	R-32-10	300.0	8	6.3	B	Asphalt	VCP						0.0	300.0		2		4	
E. 26th St.	R-45-19	R-45-20	351.0	8	11.5	D	Asphalt	VCP	107.0	101.0	113.0	12.0	Offset Pipe					1		
E. 26th St.	R-45-19	R-45-20	351.0	8	11.5	D	Asphalt	VCP						0.0	351.0		2		5	
E. 26th St.	R-45-23	R-45-24	325.7	8	5.7	A	Asphalt	VCP	41.5	38.5	44.5	6.0	Defective Service Tap/Roots					1		
E. 26th St.	R-45-23	R-45-24	325.7	8	5.7	A	Asphalt	VCP	243.6	240.6	246.6	6.0	Defective Service Tap					1		
E. 26th St.	R-45-23	R-45-22	349.7	8	6.7	B	Asphalt	VCP	295.1	292.0	298.0	6.0	Defective service line tap					1		
E. 26th St.	R-45-22	R-45-21	350.0	8	6.9	B	Asphalt	VCP	53.4	50.0	56.0	6.0	Defective service line tap					1		
E. 26th St.	R-45-28	R-45-25	371.8	8	4.8	A	Asphalt	VCP	173.7	170.0	176.0	6.0	Defective service line tap					1		
E. 27th St.	R-32-12	R-32-13	302.0	8	6.9	B	Asphalt	PVC	170.1	167.0	173.0	6.0	Defective service line tap					1		
E. 27th St.	R-32-12	R-32-13	302.0	8	6.9	B	Asphalt	PVC	260.0	227.0	302.0	75.0	Sag					2		1
E. 27th St.	R-32-13	R-32-14	372.1	8	7.9	B	Asphalt	VCP						0.0	372.1				5	

TOP HAT CONNECTIONS

STREET	BEGINNING MANHOLE	ENDING MANHOLE	DISTANCE FROM BEGINNING MANHOLE	LOCATION TOP/LT/RT
Marmillion LP	R-30-48	R-30-49	60.7	LT
			133.4	RT
			150.7	LT
W. 3rd St.	R-30-95	R-30-94	12.5	TOP
			106.0	TOP
			204.7	TOP
			232.1	TOP
W. 3rd St.	R-30-93	R-30-92	113.1	TOP
			169.6	LT
			290.0	TOP
W. 3rd St.	R-30-92	R-30-91	170.9	TOP
W. 9th St.	R-30-45	R-30-44	151.6	RT
W. 10th St. /Hwy 637	R-30-42	R-30-41	76.9	LT
			141.0	RT
W. 4th St.	R-30-70	R-30-69	153.8	TOP
			216.3	TOP
Toni St.	R-30-75	R-30-74	337.0	RT
Terrance St.	R-30-64	R-30-63	25.1	TOP
			42.0	TOP
			69.3	TOP
			86.3	TOP
Chad B. Baker	R-32-15	R-32-16	179.6	RT
			300.3	LT
Chad B. Baker	R-32-16	R-32-17	123.8	LT
			243.6	RT
Chad B. Baker	R-32-17	R-32-18	290.0	LT
Chad B. Baker	R-32-18	R-45-42	119.0	TOP
			241.8	TOP
E. 26th St.	R-32-8	R-32-9	45.2	LT
			183.9	RT
E. 26th St.	R-32-9	R-32-10	91.9	LT
			177.3	LT
Marmillion LP	R-43-3	R-43-4	30.7	LT
			187.8	RT
W. 3rd St.	R-43-27	R-30-95	5.4	LT
W. 4th St.	R-43-21	R-43-20	60.6	LT
			171.2	RT
W. 5th St.	R-43-13	R-30-67	258.5	LT
W. 5th St.	R-43-14	R-43-15	166.6	LT
			280.1	LT
W. 6th St.	R-43-11	R-43-10	193.0	RT
			263.4	LT
			360.2	TOP
W. 8th St.	R-43-7	R-43-6	121.9	LT
			188.3	RT
E. 21st St.	R-44-101	R-44-100	71.7	LT
E. 21st St.	R-44-97	R-44-96	216.0	LT
E. 22nd St.	R-44-102	R-44-103	73.1	LT
			121.7	LT
E. 22nd St.	R-44-103	R-44-104	42.0	LT
			261.9	LT
E. 23rd St.	R-44-110	R-44-112	324.9	TOP
Chad B. Baker	R-45-43	R-45-42	60.6	TOP
			201.2	TOP
E. 26th St.	R-45-19	R-45-20	220.7	TOP
			241.2	TOP
E. 27th St.	R-45-35	R-45-34	110.6	RT
			223.7	LT

STREET	RAISE MANHOLE
Godchaux Dr.	R-30-43
Godchaux Dr.	R-30-47
NW 12th St.	R-30-29
NW 15th St.	R-30-1
Toni St.	R-43-76A
W. 4th St.	R-43-18
W. 4th St.	R-43-20
W. 7th St.	R-30-58

CC-TV		
STREET	LINE	LENGTH (L.F.)
NW 13th St.	R-30-21 to R-30-20	235
E. 22nd St.	R-31-77 to R-31-77A	TBD
E. 22nd St.	R-31-77A to R-31-78	TBD
E. 22nd St.	R-31-78 to R-31-79	TBD
F.D. Jones St.	R-30-20 to R-30-26	TBD
F.D. Jones St.	R-30-26 to R-30-27	215.7
Godchaux Dr.	R-30-43 to R-30-47	TBD
W. 7th St.	R-30-59 to R-30-58	TBD

UTILITY WARNING

The Contractor is advised that existing overhead and underground utilities such as (but not limited to) electrical lines and poles, telephone cable, gas lines, water lines, and sanitary sewers exist in the rights-of-way where the proposed improvements are to be installed, all in accordance with the provisions of R.S. 38:2223. It shall be the Contractor's responsibility to protect these existing utilities during the construction of the work to be installed under this Contract and any damage to the existing utilities caused by the negligent acts of the Contractor shall be repaired by the Contractor at his expense. The Contractor shall contact Louisiana One (1) Call (1-800-272-3020) a minimum of 48 hours prior to beginning construction in the work area.

STATE OF LOUISIANA
GERALD W. BABIN, JR.
REG. No. 28785
REGISTERED
PROFESSIONAL ENGINEER
IN
CIVIL ENGINEERING
1/28/13

DATE	REVISIONS	BY	DATE	REVISIONS	BY
01/13	ISSUED FOR BID	GWB			

ST. JOHN THE BAPTIST PARISH
OWNER

WASTEWATER LINE REHABILITATION
WASTEWATER LINE REHABILITATION TABLES
TITLE

DESIGNED: GWB/KEF
DRAWN: DJM
CHECKED: CMH
APPROVED: GWB

SCALE: N.T.S.
DATE: JANUARY 2013

PROFESSIONAL ENGINEERING CONSULTANTS CORPORATION
7600 GSRI Avenue • Baton Rouge, LA 70820 • Phone: 225.769.2810 • Fax: 225.769.2882

PROJECT NO. 10929-2
SHEET NO. 9

G:\10929\10929-2\Issued for Bid\10929_09 - 11 Rehab Tables.dwg [SHT 9] Jan 28, 2013 - 3:05pm by Jae